

PROPOSED ADDITION / ADU WITHIN THE EXISTING ESTABLISHED BUILDING LINES.

NO BOUNDARY SURVEY REQUIRED *SEE OTHER SCENARIOS BELOW



SCENARIO 2:


PROPOSED ATTACHED ADDITION / ADU WHEN ANY ONE SIDE OF THE ADDITION / ADU IS WITHIN 24" OF MINIMUM SETBACK. **BOUNDARY SURVEY REQUIRED** *SEE OTHER SCENARIOS BELOW



SCENARIO 3:

PROPOSED DETACHED ADU WHEN ANY PORTION OF THE DETACHED ADU IS WITHIN 24" OF MINIMUM SETBACK.

BOUNDARY SURVEY REQUIRED *SEE OTHER SCENARIOS BELOW



SCENARIO 4:

PROPOSED NEW MAIN STRUCTURE ON A VACANT LOT <u>OR</u> IF A PROJECT IS CONSIDERED A NEW RESIDENCE BY THE BUILDING DIVISION. **BOUNDARY SURVEY REQUIRED** *SEE OTHER SCENARIOS BELOW

* OTHER SCENARIOS :

- UNDER ALL SCENARIOS, A BOUNDARY AND TOPOGRAPHIC SURVEY SHALL BE REQUIRED IF THERE IS NO EXISTING CURB, GUTTER, AND SIDEWALK ALONG THE LOT FRONTAGE. PLEASE CONTACT ENGINEERING DIVISION AT 510-494-4700 FOR SCOPE AND LIMITS OF SURVEY.
- 2. BOUNDARY AND TOPOGRAPHIC SURVEY WILL BE REQUIRED FOR ALL UNDEVELOPED FLAG LOTS.
- 3. IF A GRADING PERMIT IS REQUIRED OR TRIGGERED, A TOPOGRAPHIC SURVEY SHALL BE INCLUDED AS PART OF THE BOUNDARY SURVEY.
- 4. CITY ENGINEER, UNDER HIS/HER SOLE DISCRETION, MAY REQUIRE A BOUNDARY AND TOPOGRAPHIC SURVEY ON ANY PARCEL THAT DOES NOT MEET ANY SCENARIOS ABOVE

FIELD SURVEY
REQUIREMENTS
FOR
SINGLE FAMILY
HOME ADDITIONS
AND / OR
ACCESSORY DWELLING
UNITS (ADUs)

DATE: JANUARY 2020

SCALE: NOT TO SCALE



PLOT DATE: Jan 31, 2020 - 3:19pm FILE:

PLAT

PD

Homes

Single

Exhibit for

Requirement

Survey

C:\Users\zbalajadia\Desktop\Boundary